

Dealing with Curve Balls

Lessons learned from the Prince William Parkway/Old Bridge Intersection and 495NEXT Projects





the scariest things in life





Tell us 5 interesting things about yourself



Best I can do is I like Traffic Engineering and VASITE Conferences



Dealing with Curve Balls

Lessons learned from the Prince William Parkway/Old Bridge Intersection and 495NEXT Projects





Dealing with Curve Balls



















STARS Study Completed August 2020

- 4 Alternative Intersections Analyzed
- T-Intersection
- Thru-Cut
- Roundabout
- Flyover Interchange










STARS Study Recommended Alternative







































STARS Alternative Analysis Results

- SBL and NBT movements:
 - V/C ratio over 0.8
 - Queue exceeds storage length

	PM No-Build	PM Alternative 1
Intersection Approach		LOS (Delay (s/veh))
Prince William Parkway (EB/SB)	F (180.5)	F (80.5)
Old Bridge Road (WB)	F (104.40	E (69.7)
Prince William Parkway (NB)	F (139.1)	F (100.9)
Touchstone Circle (SB)	F (146.0)	N/A
Overall	F (147.1)	F (84.3)
	Prince William Parkway (EB/SB) Old Bridge Road (WB) Prince William Parkway (NB) Touchstone Circle (SB)	Approach Prince William Parkway (EB/SB) Old Bridge Road (WB) Prince William Parkway (NB) F (104.40 F (139.1) Touchstone Circle (SB) F (146.0)

2045 PM Build Results									
					QUEUE				
MOVEMENT	VOLUME	LOS	DELAY	V/C	DESIGNED	95 TH SIM TRAFFIC			
SBL	1460	F	139.6	1.183	340	316			
SBT	1664	А	4.9	0.427	1333*	140			
NBT	1764	D	38.5	0.991	475*	314			
NBR	450	А	0.7	0.195	200	316			
WBL	775	С	27	0.478	800*	194			
WBR	1641	А	2.7	0.553	800*	231			
OVERALL		D	39.4						









3 Alternative Intersections Analyzed


Green T

- Fails due to the high southbound left turn volume
- This creates a failure in the overall intersection that is not recoverable

Displaced left

- Shows C+ LOS for all movements
- Space constraints within the existing intersection area show significant impacts





2045 PM BUILD ALTERNATIVE LANE CONFIGURATION Prince William Parkway Old Bridge

Prince William Parkway



	Future Year (2045) Level of Service (LOS) & Delay											
Intersection Control Type		Control Type	Annroach	Lane Group	Build							
		Control Type Approach	Арргоасп			AM F	Peak		F	PM P	eak	
4 Prince William Pkwy & S			EB	Left								
				Through								
			Right									
		WB	Left	6.0	Α	2.4	_	27.0	C 43	42.2	В	
			Through-Right	0.5	Α	2.4	Α	6.6	Α	13.2		
		NB	Left			19.3						
			Through	24.2	С		В	42.7	D	34.3	C	
			Right	0.1	Α			1.3	Α			
				Left	53.0	D			52.2	D		
		SB	Through	13.0	В	28.8	С	4.9	Α	27.0	D	
				Right								
				Overall	19.1		В		24.8		С	










495NEXT Introduction



The I-495 Express Lanes Northern Extension (495 NEXT) project is a public-private partnership between the Commonwealth of Virginia and Transurban that involves extending the 495 Express Lanes north by twoand-a-half miles from the Dulles Corridor to the George Washington Memorial Parkway interchanges near the American Legion Bridge.



495NEXT Introduction



ITS Scope – VDOT and Transurban

 Replace existing and install new DMS, CCTV Cameras, Microwave Vehicle Detector Systems, Automated Incident Detection Cameras

- VDOT Fiber Duct
 Bank along project is being replaced
- March of 2023
 - Infrastructure Plans are approved as noted
 - NDC to include Fiber Details is under review

The Curve Ball






RFI from the Field

- Existing privately owned duct bank cutover will sever VDOT line
- Project Team review shows no VDOT assets being served by line, no asset sharing agreement with utility owner

Virginia State Police (VSP) Assets





- 10 Existing Cameras at American Legion Bridge at VA/MD Border
- VDOT confirms Virginia State Police License Plate Readers (LPRs) on sign gantry. VDOT is committed to providing continued VSP support



Impacts to VSP Cameras




- Existing sign gantry structure is planned to be removed and replaced by a southbound span and northbound cantilever structure
- Meeting with VSP held to discuss options, LPR camera angles, funding



Scope modifications





- Proposed revision to leave existing sign structure in place, shift proposed DMS structure 800' south
- Alleviating funding issues associated with new sign structure eased VSP coordination

Temporary Feeds



- Coordination meeting with VSP, LPR Manufacturer's Representatives, VDOT, and Design-Build team resulting in:
 - Abandoning any idea of continuing to operate fiber in private communication
 - Procurement of forward control units and modems for temporary communications, to be replaced by ultimate condition VDOT fiber, by VSP
 - Temporary outage plan is drafted by VSP

Lessons Learned



- Prompt, transparent communication early in process (when ball is "breaking") is paramount
- Be prepared to think outside of the box and use all the tools you have
- Consensus driven solutions and stakeholder buy in is key
- On Design-Build projects, clearing up funding issues early in the process facilitates inter-stakeholder coordination